

No: 1661/21/NK/TVPM

Office of the Nirmithi Kendra,  
B Block, 4th Floor, Civil Station,  
Kudappanakunnu, Thiruvananthapuram 43.  
pmnirmithi01@gmail.com, 0471-2732929  
29.09.2021

**Tender Notice for the Civil Works of District Supply office at Kadakampally Mini Civil Station**

District Nirmithi Kendra invites Competitive <sup>tenders</sup> quotations from authorized Suppliers/Individual in the form attached herewith for District Nirmithikendra's Project site at Construction of Civil Works at Kadakampally Mini Civil Station

S.No.	PARTICULARS	QTY	UNIT
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron,)	227.175	Kg
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineering-Charge.Pre-laminated particle board with decorative lamination on bothsides	44.558	Sqm
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in -Charge. ( Cost of aluminium snap beadin shall be paid in basic item):With float glass panes of 5.50 mm thickness	33.420	Sqm
4	Providing and fixing aluminium tubular handle bar 32 mm outer dia, 3.0mm thick & 2100 mm long with S.S. screws etc. complete as per direction of Engineer -in-Charge. Powder coated minimum thickness 50 micron aluminium tubular handle bar	10	nos

5	Providing and fixing 100 mm brass locks ( best make of approved quality ) for aluminium doors including necessary cutting and making good etc. complete	5	nos
6	Providing and fixing Hydraulic door closer bottle type M.S. body with necessary accessories and screws etc complete	5	nos
7	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 100x75x4 mm	15	nos
8	Providing and fixing 100mm wide vertical blinds of approved shade and texture to windows with nylon strings for adjustments and with locking arrangements including cost and conveyance of all materials, labour charges etc. complete as per standard specifications and directions of the Engineers	38.431	Sqm
9	Providing & fixing false ceiling with 12mm thick Gypsum board fixed to a grid made out of anodised aluminium T sections 35x15x1.5 mm size main runners and cross runners mm fixed to main runners placed 600mm c/c both ways so as to form a grid of 600mm square. Frame work suspended from the ceiling by level adjusting hangers of 6mm dia M.S rods fixed to roof slab by means of ceiling cleats.hangers of 6mm dia suspenders shall be placed 600x1200 mm c/c including fixing to the frame with C.P brass screws complete. Providing and fixing anodised aluminium work consisting of tee/angle sections of approved make conforming to IS :733 in frames of false ceiling including aluminium angle cleats with necessary C.P brass /stainless steel sunk screws ,aluminium perimeter angles fixed to wall with rawl plugs @ 450mm centre to centre and fixing the frame work to level adjusting hangers with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in-charge.The board is finished with filling the tapered edges of the board with joining compound etc,	30.934	Sqm
10	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	0.435	cum
11	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead.Cement mortar 1:4 ( 1 cement: 4 coarse sand)	2.701	Sqm



12	Providing and fixing I st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	3.292	Sqm
13	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.	0.270	Sqm
14	Dismantling doors, windows and clerestory windows (steel or wood ) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area 3 sq. metres and below	1	nos
15	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand): With Modular bricks	0.435	Cum
16	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 ( 1 cement : 4 fine sand)	3.781	Sqm
17	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	3.781	Sqm
18	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	3.781	Sqm
19	Office Inside Name Signage Supply and fixing charge	10	nos
20	Outside Signage	2	nos

#### 1) Bid Price

- The contract shall be for the full quantity as described above. Corrections if any shall be made by crossing out re-writing with initial and date.
- The rate should inclusive of all taxes, levies, transports etc. Unloading shall be done by District Nirmithikendra.
- Usual deduction of taxes will be made from the gross amount of bill.

- d) The rate quoted by the bidder shall be fixed for the duration of the contract and shall not be subject to adjustment on any account.
  - e) The price should be quoted in Indian rupees only.
- 2) Each bidder shall submit only one tender.

3) Validity of Tender

Tender shall remain valid for a period not less than 45 days after the dead line date specified for submission

4) Evaluation of tender

The purchaser will evaluate and compare the tenders determined to be substantially responsive ie which

- a) Are properly signed
- b) Confirm to the terms and conditions and specification.

5) Award of Contract

a) The purchaser will award the contract to the bidder whose tenders has been determined to be substantially responsive and who has offered the Lowest evaluated tender price


b) Not with standing above, the purchaser reserves the right to accept or reject any tenders and to cancel the bidding process and reject all tenders at anytime prior to the award of the contract

c) The bidder whose bid is accepted will be notified of the award of the contract by the purchaser prior to expiration of the tender validity period. The terms of the accepted offer shall be incorporated in the purchase order.

6) The amount will be released after verification of the material in physical, quality and receipt of invoice in this office according to the availability of funds. Individual or authorized dealers/agents are only eligible.

7) You are requested to provide your offer latest by 12 hours on **06.10.2021** and the tender will be opened at **06.10.2021**.

We look forward to receiving your tenders and thank for your interest in this work.

  
Project Manager



Format of Tender

S.No.	PARTICULARS	QTY	UNIT	Amount in figures	Amount in words
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing /paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, paneling and dash fasteners to be paid for separately): For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron,)	227.17 5	Kg		
2	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS : 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineering-Charge.Pre-laminated particle board with decorative lamination on bothsides	44.558	Sqm		
3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer - in - Charge. ( Cost of aluminium snap beadin shall be paid in basic item):With float glass panes of 5.50 mm thickness	33.420	Sqm		
4	Providing and fixing aluminium tubular handle bar 32 mm outer dia, 3.0mm thick & 2100 mm long with S.S. screws etc. complete as per direction of Engineer -in-Charge. Powder coated minimum thickness 50 micron aluminium tubular handle bar	10	nos		
5	Providing and fixing 100 mm brass locks ( best make of approved quality ) for aluminium doors including necessary cutting and making good etc. complete	5	nos		

6	Providing and fixing Hydraulic door closer bottle type M.S. body with necessary accessories and screws etc complete	5	nos		
7	Providing and fixing ISI marked aluminium butt hinges anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 100x75x4 mm	15	nos		
8	Providing and fixing 100mm wide vertical blinds of approved shade and texture to windows with nylon strings for adjustments and with locking arrangements including cost and conveyance of all materials, labour charges etc. complete as per standard specifications and directions of the Engineers	38.431	Sqm		
9	Providing & fixing false ceiling with 12mm thick Gypsum board fixed to a grid made out of anodised aluminium T sections 35x15x1.5 mm size main runners and cross runners mm fixed to main runners placed 600mm c/c both ways so as to form a grid of 600mm square. Frame work suspended from the ceiling by level adjusting hangers of 6mm dia M.S rods fixed to roof slab by means of ceiling cleats.hangers of 6mm dia suspenders shall be placed 600x1200 mm c/c including fixing to the frame with C.P brass screws complete. Providing and fixing anodised aluminium work consisting of tee/angle sections of approved make conforming to IS :733 in frames of false ceiling including aluminium angle cleats with necessary C.P brass /stainless steel sunk screws ,aluminium perimeter angles fixed to wall with rawl plugs @ 450mm centre to centre and fixing the frame work to level adjusting hangers with necessary cadmium plated machine screws all complete as per approved architectural drawings and direction of the Engineer-in-charge.The board is finished with filling the tapered edges of the board with joining compound etc,	30.934	Sqm		
10	Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge.In cement mortar	0.435	cum		
11	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 meters lead:Cement mortar 1:4 ( 1 cement: 4 coarse sand)	2.701	Sqm		



12	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer -in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3 kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	3.292	Sqm		
13	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.	0.270	Sqm		
14	Dismantling doors, windows and clerestory windows (steel or wood ) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead: Of area 3 sq. metres and below	1	nos		
15	Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand): With Modular bricks	0.435	Cum		
16	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 ( 1 cement : 4 fine sand)	3.781	Sqm		
17	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	3.781	Sqm		
18	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade: Two or more coats on new work	3.781	Sqm		
19	Office Inside Name Signage Supply and fixing charge	10	nos		
20	Outside Signage	2	nos		

Gross Total Cost: - Rs. ....

(In words) We agree to supply the above goods in accordance with the technical Specification for a total price of Rs. .... (amount in figure) .... (amount in words) with in the period specified in the invitation for tender.

**Signature of Supplier**